

**MATERIAL QUANTITY / COST ESTIMATE FOR THE CONSTRUCTION
OF ONE RAIN BOOTS STAND**

S/N	DESCRIPTION	UNIT	QTY
A	<u>PRELIMINARY</u>		
1-	Mobilization and demobilization	Ls	1
B	<u>METAL WORKS</u>		
1-	1 1/4" galvanized iron pipe	No	6
2-	∅12mm steel rod	No	2
3-	∅3.5mm electrode (SAF)	Pkt	1
4-	Cutting disc	No	1
5-	Grinding disc	No	1
6-	Anti rust for 1st coat painting	Kg	2
7-	Aluminium paint for 2nd coat painting	Kg	2
8-	White spirit	Lt	2
9-	4" painting brush	No	2
	Material cost		
10-	Provision for labour and overhead 25% of metal works	Ls	1

SUMMARY

S/N	DESCRIPTION	
A	PRELIMINARY	
B	METAL WORKS	
	TOTAL	

Prepared by: _____

Checked by: _____

