


Lot 1

TENDER**CAMEROON DEVELOPMENT CORPORATION
GROUP BANANA****QUANTITY/COST ESTIMATE FOR ESSOASSOA IRRIGATION INSTALLATION**

S/N	DESCRIPTION	UNIT	QTY	UNIT PRICE (FCFA)	TOTAL AMOUNT (FCFA)
1	PE D40mm low density in rolls of 200m (PN 4 bar)	ROLL	111		
2	Teflon tape	NO	350		
3	Saddle D40mm X 1/2" female threaded	NO	610		
4	D40mm connector	NO	1300		
5	Base riser (1/2" X 30 cm, male threaded at one end and slanted at 45° AT one end)	NO	400		
6	Tee D90mm	NO	70		
7	PVC glue	KG	20		
8	PVC pressure collar 3" PN 16	NO	80		
9	Flange 3" PVC	NO	80		
10	PE pressure collar + flange 3"	NO	240		
11	Saddle D90mm x 1" Female threaded	ML	400		
12	Saddle 90 X 2"	NO	80		
13	Ball valve 2" M F	NO	80		
14	Gasket DN 200	NO	4		
15	Regulation valve DN 200	NO	2		
16	Gate valve DN 500	NO	1		
17	Flange DN 50 PN 16	NO	2		
18	Bolt 24 x 100	NO	40		
19	Gasket DN 50	NO	2		
20	Adaptator PE 40mm M	NO	1300		
21	Filtre à tamis en metal DN200 500micron (voir photo)	NO	2		
22	Kit contrelavage automatique des filtres	NO	2		
23	Coude 90 acier DN200 90 degrees	NO	8		



Lot 1

24	Bride acier A S DN200 PN16	NO	8		
25	Boulons 20x100 plus ecrous	NO	80		
26	Joint plat DN200	NO	20		
27	Equipements automatisme telaqua	NO	80		
28	3" pvc riser (threaded both ends, 1m long)	No	100		
	<u>Materiel pour la Station de Fertigation</u>				
29	Pompe doseuse injecteur Amiad duplex 4-03 plus accessoires	NO	4		
30	Cuves de 1000litres	NO	8		
31	Vanne BS inox 3/4"MF	NO	8		
32	Mammelon à AS 3/4"	NO	8		
33	Tuyau PE DN25	M	100		
34	Kit de pieces de rechange	NO	8		
35	Tubes des graisse	FLACON	20		
	TOTAL				



Tp

[Handwritten signature]
GMB